

**BRUNSWICK HIGH SCHOOL  
FOOTBALL FIELD HOUSE RENOVATIONS / ADDITIONS**

**ADDENDUM NO. 3**

**DATE: September 27, 2017**

John A. Tuten & Associates, Inc.  
4680 Hwy 17 North  
Brunswick, GA 31525

---

**GENERAL**

1. The concrete slab under what will become the new Assistant Coaches space # 112, will need to be removed and replaced in order to level the floor.
2. Where new hollow metal frames are installed in existing masonry, saw cut the opening and use knock down hollow metal frames. Where existing opening are to be infilled with masonry, tooth the existing masonry the install the new.
3. The new wall hung heat pumps being installed in the existing building, the duct openings will require a lintel similar to Detail one on A3.2 "Head Detail".
4. The Owner will pay for any fees charged by Brunswick Glynn Joint Water and Sewer Commission for water and sewer related services.
5. All floor tile is a 6" X 6" quarry tile. CT-1 is a thick set quarry and CT-2 is a thin set quarry. Drawing A8.0 shows the Crosshatched area where the CT-1 thick set till will be installed. In Room 108 the area under the showers will be recessed for thick set tile. Other areas in the existing building where floors are removed to install new plumbing, we will provide slope to floor drains in the new concrete and the floor tile will be thin set.
6. Toilet partitions are Solid Plastic per Section 102113.19. Note on Detail 16 sheet A16.0 is incorrect.

**DRAWINGS**

**1. A3.1 – DOOR SCHEDULE**

- A. Doors marked "MF" in the Door schedule should be "SF". These are steel Flush Hollow metal doors.
- B. Doors 107, 107A, 107B, 113, and 115 are existing and should be marked so in the Door Schedule. These openings in the Base Bid will receive paint and adjusted hardware. Alternate #2 would install new fiberglass doors and frames at openings 107, 107A, 113, and 115 and new wood doors at opening 107B. The cost of the new hardware scheduled for these doors should be included in the Alternate #2 pricing.
- C. In the "Glass Type Notes" – delete item #3. All glazing is 1/4" clear glass as called out in Note #2.

**GLYNN COUNTY  
BRUNSWICK HIGH SCHOOL BASEBALL GRADING & DRAINAGE**

**2. A7.0 – WALL SECTION DETAILS**

A. Details #3 & #6 will require wood blocking around the edge of the canopies.

**3. A9.0 – MILLWORK ELEVATIONS AND DETAILS**

A. Details 12, 13, 14, 15 & 17 call out Pre Formed Laminate tops. This is incorrect.  
All tops and back splashes are solid surface material.

**END OF ADDENDUM NO. 3**

**Attachments:**

1706\160\170927AddendumNo3