

**GLYNN COUNTY STADIUM
SITE WORK**

ADDENDUM NO. 1

John A. Tuten & Associates, Inc.
4680 Hwy 17 North
Brunswick, GA 31525

DATE: April 17, 2018

GENERAL

1. The following clarifies the responsibilities of the Building Contractor and the Site Contractor:

SHEET C1.1 – DEMOLITION PLAN

- A. All of the work described on the Demolition Plan is either to be done by the Owner or by the Site Contractor.

SHEET C2.1 – ENLARGED DEMOLITION PLAN

- A. All of the concrete sidewalk work shown connected to the building and extending to the edge of parking is to be the responsibility of the Building Contractor.
- B. The paving and striping work adjacent to the concrete sidewalks will be the responsibility of the Site Contractor and that work will be installed by the Site Contractor after the Building Contractor installs the sidewalks. The Building Contractor must have the sidewalks installed by May 1, 2019 so that the Site Contractor can install paving work to be completed not later than August 1, 2019.

SHEET C3.1 – ENLARGED GRADING AND DRAINAGE PLAN

- A. All of the storm drainage work will be installed by the Site Contractor.
- B. Structures D22, D21, D20, D19 draining into existing Structure E1 will be completed and the disturbed work sodded not later than July 27, 2018, so that the field is ready for football season to begin in August 2018.
- C. Structures D42 and D41 draining into D22 and Structure D40 draining into existing Structure E1, will be accomplished after the exterior building work is substantially complete but before the sidewalk work is installed by the Building Contractor.

SHEET C4.1 – ENLARGED UTILITY PLAN

- A. The new domestic water line work beginning with interrupting the existing water line and tying in a 4” valve and then extending 4” water around the building to point 5’ from the new building must be installed by July 20, 2018. The Owner will extend temporary water into the field house from the cut off valve installed by the Site Contractor.
- B. The sanitary sewer work will be installed by the site contractor to the building connection location, 8 feet from the building wall line. The building contractor will make the final connection into the sanitary sewer.

**GLYNN COUNTY STADIUM
SITE WORK**

END OF ADDENDUM NO. 1

Attachments:

1708SiteWork\160\180417AddendumNo1