

**ADDENDUM NO. 2**

John A. Tuten & Associates, Architects  
4680 Hwy 17 North  
Brunswick, GA 31525

---

**PROJECT MANUAL**

**1. SECTION 014000 – QUALITY REQUIREMENTS**

- A. At Part 1.1, Summary – Add the following:
  - “B. The Owner will hire and pay quality control testing firm to accomplish the following:
    - 1. Monitor proof rolling and identifying and directing removal of unsatisfactory materials.
    - 2. Testing borrow pit material and approving borrow material prior to material being placed on the site.
    - 3. Monitoring and testing soil compaction.
    - 4. Conduct inspections and prepare reports required for monitoring erosion control procedures.
- C. Contractor’s responsibility:
  - 1. Notify Architect and Owner’s engineering testing firm 24 hrs. in advance of activities requiring monitoring and testing.
  - 2. Provide access to the work.
  - 3. Pay the costs of retesting for work not complying with contract documents.”
- B. At Part 1.1, Summary – Item “B.” becomes “D.”.

**END OF ADDENDUM NO. 2**

1903Ph2\160\190425AddendumNo2